

ITEM	DESCRIPTION	QTY	UNIT	RATE	TOTAL
	<u>RENOVATION WORKS</u>				
	<u>DEMOLITION</u>				
A	carefully demolish existing wall surface (10 SM) and set aside all arising materials		ITEM		
	<u>REINFORCED CONCRETE WORKS</u> <u>(ALL PROVISIONAL)</u>				
	<u>Vibrated reinforced concrete</u> <u>(1:2:4/20 - 20mm aggregate) as</u> <u>described in:-</u>				
B	100 mm thick slab	20	SM		
	<u>Steel reinforcement bars</u> <u>including bending, hooks, tying wire, cutting, spacer</u> <u>blocks and supporting all in position</u>				
	<u>High tensile square twisted bars to</u> <u>B.S. 4461 as described in :</u>				
C	10 mm Diameter bar	220	KG.		
	<u>Sawn formwork as described to :</u>				
D	soffits of slab	20	SM		
	<u>INTERNAL PAINTING</u>				
	<u>Scrub existing painted plastered surfaces to make it</u> <u>loose and free of dirt, prepare and apply two finishing</u> <u>coats 'duracoat or crown " plastic silk Vinyl matt or</u> <u>equivalent emulsion paint on:-</u>				
E	Walling	253	SM		
	<u>EXTERNAL FINISHES</u>				
F	Extra over horizontal and vertical pointing in 24mm thick rod in cement and sand (1:3) mortar	150	SM		
G	Hack out joints and apply 15 mm thick gauged lime plaster (1:2:9) in two coats finished with steel trowel on natural stone gable walls and beams	25	SM		
	<u>Scrub existing painted plastered surfaces to make it</u> <u>loose and free of dirt, prepare and apply two finishing</u> <u>coats 'duracoat or crown " plastic silk Vinyl matt or</u> <u>equivalent emulsion paint on:-</u>				
E	Gable Walling , beams , windows and door reveals	25	SM		
	TOTAL CARRIED TO SUMMARY				

ITEM	DESCRIPTION	QTY	UNIT	RATE	TOTAL
	<u>ROOFING AND DAILY WATER GOODS</u>				
	<u>Prepare and Apply Three Coats of Gloss Oil Paint to:-</u>				
A	Fascia board surfaces 200 - 300mm girth	34	LM		
B	prepare and apply two coats of roof paint to the existing iron sheets	187	SM		
	<u>Rain Water disposal</u>				
	<u>The following in plastic rainwater</u>				
A	150 x 100 mm plastic half round gutter fixed to fascia board with and including approved pattern brackets at 1000 mm cc	34	LM		
B	<u>Extra over</u> gutter for stopped end piece with 100 mm diameter outlet	4	NO		
C	100mm diameter plastic downpipe fixed to natural stone walling with and including mild steel brackets 600mm centres	12	LM		
D	<u>Extra over</u> down pipe for 100 mm diameter swan neck wall off set	4	NO		
E	<u>Extra over</u> down pipe for 100 mm diameter rain water shoe	4	NO		
	<u>TOTAL FOR ROOFING AND RAIN WATER GOODS CARRIED TO SUMMARY</u>				

ITEM	DESCRIPTION	QTY	UNIT	RATE	TOTAL
	<u>RENOVATION WORKS</u>				
	<u>SUMMARY</u>				
		PAGE	NO		
1	INTERNAL AND EXTERNAL FINISHES	RW	1		
2	ROOFING	RW	4		
3	FLOOR FINISHES	RW	5		
	<u>TOTAL FOR</u>				
	<u>RENOVATION WORKS</u>				
	<u>CARRIED TO GRAND SUMMARY</u>				

ITEM	DESCRIPTION	QTY	UNIT	RATE	TOTAL
<u>CHAINLINK FENCING</u>					
<u>ELEMENT NO: 1</u>					
(ALL PROVISIONAL)					
A	Clear the site and cut down the small trees and shrubs along the fence line and grab up their roots.	56	SM		
B	14 gauge x 2100 mm high chainlink woven mesh wire to 5 no . Strand barbed wire	56	LM		
C	Gauge 12 Barbed wire in 5 no strands	280	LM		
D	Supply and fix concrete posts 150mm dia x 3000mm long fencing posts held to ground in mass concrete sorround 600 mm deep spaced at 3000 mm centres,including all excavations and spreading excavated materials.	19	NO		
E	2.0 M long strutting posts; one end anchored to main fence post (m.s); other build into concrete sorround strutting at 20 m centres and corners	10	NO		
F	Supply and fix 3000 x 3000 mm high Pre- painted steel gate as directed by the project manager		ITEM		
<u>TOTAL FOR CHAINLINK FENCING BROUGHT TO SUMMURY</u>					

ITEM	DESCRIPTION	QTY	UNIT	RATE	TOTAL
<u>PROVISIONAL SUMS</u>					
A	Allow a provisional Sum for Project Management Administration Team Expenses	SUM			20,000.00
B	Allow a provisional Sum for Project Management Committee Team Expenses	SUM			25,000.00
C	Allow a provisional sum for contingencies	SUM			30,000.00
D	Allow a Provisional sum for project sign board and approved by Project Manager, overall size 1200 x 1200mm, 6mm plate held to the ground by 2No posts made of 25 x 25 x 4mm RHS firmly secured to the ground using concrete 1:3:6 including all necessary excavations and load cart away, painting in 3 coats oil paint.	SUM			15,000.00
E	Allow a Provisional Sum for reinforcing 2no doors using D16 bars				10,000.00
F	Allow a provisional sum for supplying and fixing w/C , 2no manholes and manhole covers and drainage works				150,000.00
TOTAL FOR PROVISIONAL SUMS CARRIED TO GRAND SUMMARY					250,000.00

ITEM	DESCRIPTION	QTY	UNIT	RATE	TOTAL
<u>GRAND SUMMARY</u>					
		PAGE	OFFICIAL USE	TENDERER'S USE	
	<u>PRELIMINARIES</u>				
1	Particular and General Preliminaries				
	<u>BUILDERS WORKS</u>				
2	Builders Works	BW/18			
3	Chainlink Fence				
	<u>PROVISIONAL SUMS</u>				
4	Provisional Sums	BW/22			
	Sub - Total		KSHS.		
	GRAND TOTAL CARRIED TO FORM OF TENDER		KSHS.		

NAME OF TENDERER.....

ADDRESS.....

SIGNATURE.....STATUS.....

DATE.....

NAME OF WITNESS.....

ADDRESS.....

SIGNATURE.....

DATE.....