

ITEM	DESCRIPTION	QTY	UNIT	RATE	TOTAL
	<u>BUILDERS WORKS</u>				
	<u>MULTI PURPOSE HALL</u>				
	<u>ELEMENT NO. 1</u>				
	<u>SUBSTRUCTURE {All Provisional}</u>				
A	Excavate to reduce level in normal soil for strip not exceeding 1.50 M deep average 250mm deep from the stripped level.	85	CM		
	<u>Filling</u>				
B	300mm thick hardcore filling; well watered and compacted to 100% maximum dry density; in layers not exceeding 150mm thick all to Engineer's directions and satisfaction	344	SM		
	<u>Blinding</u>				
C	50 mm Stone dust blinding to surfaces of hardcore rolled smooth to receive polythene damp proofing membrane	344	SM		
	<u>Insecticide treatment</u>				
D	"TERMIDOL" or other equal and approved chemical insecticide treatment prepared and applied according to the manufacturer's printed instructions.	344	SM		
	<u>Damp proof membrane</u>				
E	500 Gauge polythene or other equal and approved plastic sheet damp proof membrane laid over blinding(measured nett - allow for laps)	344	SM		
	<u>Vibrated reinforced concrete</u> <u>(1:2:4/20-20mm aggregate) as described in:</u>				
F	100mm Thick ground floor slab	344	SM		
	<u>Mesh reinforcement</u>				
G	Fabric mesh reinforcement to B.S. 4483 ref: A66 including laps tyingwire and spacer blocks complete(measured nett-allow for laps)	344	SM		
	<u>TOTAL FOR</u> <u>ELEMENT NO. 1</u> <u>SUBSTRUCTURE</u> <u>CARRIED TO SUMMARY</u>				

ITEM	DESCRIPTION	QTY	UNIT	RATE	TOTAL
A	<p><u>ELEMENT NO. 3</u></p> <p><u>WALLING</u> <u>(ALL PROVISIONAL)</u></p> <p><u>Fine chiselled natural stone walling bedded and jointed in cement and sand (1:3) mortar and reinforced with and including 20swg x 25mm wide hoopiron;</u></p> <p>200mm Thick reinforced in every third course externally</p>	110	SM		
	<p><u>TOTAL FOR</u> <u>ELEMENT NO. 3</u> <u>WALLING</u> <u>CARRIED TO SUMMARY</u></p>				

ITEM	DESCRIPTION	QTY	UNIT	RATE	TOTAL
	<p style="text-align: center;">BUILDERS WORKS</p> <p style="text-align: center;"><u>SUMMARY</u></p>				
1	SUBSTRUCTURES	PAGE	NO		
2	WALLING	BW	1		
		BW	2		
	<p style="text-align: center;">TOTAL FOR BUILDERS WORKS CARRIED TO GRAND SUMMARY</p>				

ITEM	DESCRIPTION	QTY	UNIT	RATE	TOTAL
<u>PROVISIONAL SUMS</u>					
A	Allow a provisional Sum for Project Administration Team Expenses		SUM		20,000.00
B	Allow a provisional Sum for Project Management Committee Team Expenses		SUM		30,000.00
C	Allow a provisional sum for contingencies		SUM		5,000.00
TOTAL FOR PROVISIONAL SUMS CARRIED TO GRAND SUMMARY					55,000.00

ITEM	DESCRIPTION	QTY	UNIT	RATE	TOTAL
	<u>GRAND SUMMARY</u>				
		PAGE	OFFICIAL USE	TENDERER'S USE	
	<u>PRELIMINARIES</u>				
1	Particular and General Preliminaries				
	<u>BUILDERS WORKS</u>				
2	Builders Works	BW/5			
	<u>PROVISIONAL SUMS</u>				
3	Provisional Sums	BW/6			
	Sub - Total	KSHS.			
	GRAND TOTAL CARRIED TO FORM OF TENDER	KSHS.			

NAME OF TENDERER.....

ADDRESS.....

SIGNATURE..... STATUS.....

DATE.....

NAME OF WITNESS.....

ADDRESS.....

SIGNATURE.....

DATE.....