

ITEM	DESCRIPTION	QTTY	UNIT	RATE
	<b><u>PROPOSED IMPROVEMENT AND RENOVATION WORKS TO 6 NO CLASSROOM BLOCK AT FATHER TIELEN SCHOOL IN SUBA NORTH SUB COUNTY</u></b>			
	<b><u>SECTION 1:</u></b>			
	<b><u>REMOVALS, HACKINGS, TAKE OUTS AND CLEANING EXISTING SURFACE</u></b>			
	<b><u>Carefully hack out the following finishes and cart away debris arising there from:</u></b>			
A	Existing cement /sand screed to floor	516	Sm	
B	Existing sand cement render to plinth area	62	Sm	
	<b><u>the following painted surfaces in readiness for new finish</u></b>			
C	Vertical sides of internal walls	478	Sm	
D	Ditto external walls	438	Sm	
E	Ditto window girth	108	Sm	
F	Metal surfaces Door	36	Sm	
G	200X25 mm fascia board	79	Sm	
	<b>Carried to Collection</b>			<b>Kshs</b>

FTSS/REN/PG1

ITEM	DESCRIPTION	QTTY	UNIT	RATE
	<b><u>Section 4</u></b>			
	<b><u>WINDOWS</u></b>			
	<b><u>Glazing</u></b>			
A	4mm thick clear sheet glass in panes 0.1 -0.5m2 fixed to steel window panes with putty	68	Sm	1000
	<b><u>Supply and Fix</u></b>			
B	Window fasteners	32	No	300

C	Brass Window Stays	32	No	300
<b>Carried to Collection</b>				<b>Ksh</b>

FTSS/REN/PG2

ITEM	DESCRIPTION	QTTY	UNIT	RATE
<b><u>SECTION 5</u></b>				
<b><u>FINISHES</u></b>				
<b><u>Floor</u></b>				
A	38mm thick cement and sand (1:3) screed to receive floor tiles	516	Sm	350
<b><u>300x300x6mm coloured ceramic floor tiles as manufactured by SAJ' or other equal and approved on cement backing and pointing and joining in matching cement grout to :</u></b>				
B	Floor	518	SM	1000
C	100mm high Ditto skirting	192	Lm	300
<b><u>Plinth</u></b>				
D	15mm thick cement sand (1:3) render to plinth area	68	Sm	325
<b><u>Painting and Decoration</u></b>				
E	Apply three coats of vinyl paint to wall surface internally	478	Sm	250
F	Apply two coats of first grade plastic emulsion paint to wall externally	438	Sm	250
<b><u>Fascia and Verge Board</u></b>				
G	Prepare and apply two coats of first quality gloss oil paint to Timber surface	79	Sm	150
H	Apply two coats of bituminous black paint to plinth area	69	Lm	300
I	Apply two coats of first grade gloss oil paint to rendered surface of window sill	54	Lm	150
<b><u>Doors</u></b>				
J	Apply two coats of quality gloss oil paint to metal surfaces	38	Sm	150
<b><u>Window</u></b>				
K	Prepare and apply two coats of first quality gloss oil paint to metal window surface	108	Sm	150
<b><u>Black Wall</u></b>				
L	Prepare and apply two coats of black board paints to plastered surface	36	SM	150

			Ksh
--	--	--	-----

FTSS/REN/PG3

ITEM	DESCRIPTION	
<b><u>SUMMARY OF COLLECTION</u></b>		
A	TOTAL FOR COLLECTIONS FROM <i>LS/REN/ Page 1</i>	
B	TOTAL FOR COLLECTIONS FROM <i>LS/REN/ Page 2</i>	
C	TOTAL FOR COLLECTIONS FROM <i>LS/REN/ Page 3</i>	
<b>TOTAL FOR COLLECTIONS (BUILDER'S WORK)</b>		
<b>CARRIED TO COLLECTIO SUMMARY</b>		

FTSS/REN/PG4

ITEM	DECSRIPTION	AMOUNT ( KSHS
	<u>PROVISIONAL SUMS</u>	

A	Allow for a provisional sum of Kenya shillings thirty thousand for contingencies	
TOTAL FOR PROVISIONAL SUMS CARRIED TO SUMMARY		

FTSS/REN/PG5

ITEM	DESCRIPTION	FOR OFFICIAL USE (KSHS.)
<b><u>GRAND SUMMARY</u></b>		
A	Builder's work from LS/REN/ Page 6	-
B	Provisional sums from LS/ REN/ Page 7	30,000.00
<b>Sub - Total</b>		
Add 16% V A T		
C	Project Management By PMC	30,000.00
D	Project Supervision	20,000.00
E	Project Documentation	1,000.00
F	Project branding & erection of sign post	20,000.00
<b>GRAND TOTAL</b>		
<b>CARRIED TO FORM OF TENDER</b>		

Amount in words Kenya : .....

Tender's Name:.....

**Address:**.....

**Signature & Stamp:**.....

**Date:**.....

**Witness Name:**.....

**Address:**.....

**Signature:**.....

**Date:**.....

---

**FTSS/REN/PG6**







30,000.00

30,000.00

FOR  
CONTRACTOR'S  
USE (KSHS.)

,

..

..

...

..

.

..

..

.

---